



Jetty Tee No.3 Dolphins – Repairs

PROJECT DETAILS

Centrals were engaged in a design and construct contract to facilitate repair works to the Berthing Dolphins of Jetty Head Number 3 as part of the Jetty Upgrade and Modernisation Project (JUMP), whilst maintaining full operational capacity of facility.

Scope included; temporary scaffold access, enclosed hot work habitat, supply & install new pile barrel extension to extend existing 1050mm dia piles to within new upgrade element, remove, modify and replace miscellaneous steel work items, form and pour new slab including substrate preparation, reinforcement, form work and concrete placement and remediation of drummy concrete on dolphin side walls.



Client: BP Refinery (Kwinana)

Location: Kwinana, WA

Duration: 8 months

Completion: February 2012

Value: \$1.4m



PROJECT HIGHLIGHTS

Personnel on Site: 12

Manhours: 11,420